

Ringgold County Board of Supervisors Minutes

August 9, 2021

The Ringgold County Board of Supervisors met in regular session Monday, August 9, 2021. The meeting was called to order at 9:00 A.M with the following members present: Ron Landphair, Colby Holmes and Steve Knapp.

A motion was made by Knapp, second by Holmes to approve the agenda.
AYES: Unanimous NAYS: None

Engineer Jared Johnson met with the Board to provide secondary roads updates. Farm-to-Market rock was hauled to the Northwest and South-Central maintainer districts. The mower tractors were out mowing hard surface and gravel roadsides in the Southern part of the County.

The new J55 seal coat roadway required no additional attention this past week. The roadway will continue to be monitored for further bleeding.

Shoulder work was conducted along P33 South of Diagonal. High shoulder edges were cut off, allowing water to enter the ditches, and prevent secondary ditches from forming along the pavement edges. Material cut off was removed from the site and additional shoulder rock was placed.

Work order 786: Clear brush and re-shape ditches on 190th Ave. Located on 190th Ave. South of 110th Street. (Complete)

Johnson stated the department is awaiting the contractor's signature on the contract for the Redding weir project.

The department submitted pre-audit documentation, final working day report, semi-final pay voucher, and certification of completion and final acceptance of work to the Iowa DOT for the Routh box project. The DOT will review the pre-audit documentation to determine if and audit is required. It is anticipated that this project will be selected for and audit since this is the first project by a new engineer. The contractor will review the semi-final pay voucher. It is at this point any discrepancies in paid quantities will be settled.

The department began working on bridge design details for the Union 6 project, and developing the plan set.

The J23 and P64 sealcoat project will entail applying additional sealcoat lifts and HMA leveler courses at culvert depressions to J23 from Diagonal to HWY 169 and P64 from HWY 2 to J20. This project will utilize Farm-to-Market funds. The department has activated these projects in Project Development, and requested that the projects be tied together. Plans for these projects are being developed.

At the Middle Fork 19 site, last week the crew poured and stripped formwork at the east abutment, abutment slopes were shaped, revetment was placed on the abutment slopes, superstructure materials and formwork was hauled to the site. This week, the plan is to place backwall forms, set beams, place abutment diaphragm forms, tie abutment

diaphragm steel, install beam diaphragms, and start decking. Beams are scheduled to be delivered Tuesday, August 10th.

The Board approved to appoint Marlene Tull to the Historical Commission.

The Board tabled approval of claims.

RESOLUTION RC21-141

WHEREAS, the Ringgold County Board of Supervisors do hereby approve to appoint Marlene Tull to the Historical Commission.

THEREFORE, a motion was made by Knapp and seconded by Holmes stating such.


The vote on the resolution: AYES: All. NAYS: None.

ATTEST: Amanda Waske, Auditor. Passed and approved August 9, 2021

Knapp moved to approve the August 2, 2021 minutes. Holmes second. Motion carried.

Holmes moved to approve the minutes. Knapp second. Motion carried.

There was no further business. A motion was made by Knapp and second by Holmes to adjourn the meeting at 12:13 p.m.



Board of Supervisors

ATTEST:



Ringgold County Auditor