

Ringgold County Board of Supervisors Minutes September 27, 2021

The Ringgold County Board of Supervisors met in regular session Monday, September 27, 2021. The meeting was called to order at 9:00 A.M with the following members present: Ron Landphair, Colby Holmes and Steve Knapp.

A motion was made by Knapp, seconded Holmes to approve the agenda.

AYES: Unanimous NAYS: None

Engineer Jared Johnson met with the Board to provide secondary roads updates. Spot rock was hauled to the Northwest, North Central, and Southwest Maintainer districts. The mower tractor was out mowing Farm-to-Market gravel and paved roadsides in the Northern part of the County. The patcher was out working in the Southwest and Northeast parts of the County. The sign truck was out repairing deteriorated/damaged signs. Work order updates are as follows:

Work order 705: Replace deteriorated 3'x3' concrete box culvert and 24" CMP culvert protrusion with two separate 24" and 36" ADS crossroad culverts. Armor outlet with revetment. Located at the intersection of 205th Ave and 240th Street. (In Progress)

Work order 824: Clear brush and re-shape ditches and roadway for approximately ½ mile. Replace deteriorated 42" CMP culvert with new 42" ADS culvert. Located on Ringgold/Decatur Ave north of HWY 2. (Complete)

Work order 825: Replace deteriorated 24" CMP culvert with new 24" ADS culvert. Protect outlet and inlet with revetment. Located on 215th Street between 330th Ave and Decatur/Ringgold Ave. (Complete)

Work order 826: Replace deteriorated 24" CMP culvert with new 24" ADS culvert. Protect outlet and inlet with revetment. Located on 215th Street between 330th Ave and Decatur/Ringgold Ave. (Complete)

The department has reached out to the Iowa Department of Homeland Security and Emergency Management inquiring as to the status of our projects. The IDHSEMA is submitting an improved project request to attempt to have additional costs incurred to repair the facility properly paid for.

Last week the Contractor continued to work on channel excavation and revetment placement on the Redding Weir project. Weir numbers 7 & 8 were completed along with channel bank armoring between the weirs. The contractor began on construction of weir 6.

The department waiting on one additional material certification from the contractor on the Washington 20 project before turning the pre-audit paperwork into the Iowa DOT for review. The department received confirmation from the Iowa Dot that the Routh Box project has been closed out at the District/Regional level and sent to the Bureau of Finance for processing.

The department has completed the hydraulic analysis and preliminary design for the Monroe project site. A 9'-6 x 70'-0 R.R. tanker car at 25 deg. skew will hydraulically satisfy design discharges. The department has again reached out in search of a R.R. tanker.

The project will entail applying additional sealcoat lifts and HMA leveler courses at culvert depressions to J23 from Diagonal to HWY 169 and P64 from HWY 2 to J20. This project will utilize Farm-to-Market funds. These two projects will be tied together. Check plan comments have been received by the Iowa DOT on both projects. Only minor changes were requested on one of the projects. The department has obtained the required work within the ROW permits from the Iowa DOT.

The department is proposing an 80'-0 x 26' single span PPCB bridge at 0 deg skew for project L-UNION06(1)--73-80. The bridge will be replaced on the current alignment. The department has completed the final plans and bid documents for the project. The project will be publicly advertised with a letting date set for September 27, 2021. The department received no responsive bidders for the project. Therefore, as permitted by the Iowa Code the department will construct the project internally. Estimated project cost is \$215,785 which includes all material, equipment, and labor costs.

The Board approved claims to be paid September 22, 2021.

RESOLUTION RC21-163

WHEREAS, Ringgold County publicly advertised for bids for Project L-UNION06(1)—73-80, and no bids were received, the Secondary Roads department will proceed to construct the project as planned in house as allowed by the code of State of Iowa.

THEREFORE, a motion was made by Knapp and seconded by Holmes stating such.

The vote on the resolution: AYES: All. NAYS: None.

ATTEST: Korbie Rinehart, Deputy Auditor. Passed and approved September 27, 2021

RESOLUTION RC21-164

WHEREAS, the Ringgold County Board of Supervisors do hereby approve claims paid Wednesday, September 22nd, 2021.

THEREFORE, a motion was made by Holmes and seconded by Knapp stating such.

The vote on the resolution: AYES: All. NAYS: None.

ATTEST: Korbie Rinehart, Deputy Auditor. Passed and approved September 27, 2021

Holmes moved to approve the minutes and Knapp seconded. Motion carried.

With no further business, a motion was made by Knapp and seconded by Holmes to adjourn the meeting at 11:50 a.m.


Board of Supervisors

ATTEST:


Ringgold County Deputy Auditor