

Ringgold County Board of Supervisors Minutes October 11, 2021

The Ringgold County Board of Supervisors met in regular session Monday, October 11, 2021. The meeting was called to order at 9:00 A.M with the following members present: Ron Landphair, Colby Holmes and Steve Knapp.

A motion was made by Knapp, seconded Holmes to approve the agenda.
AYES: Unanimous NAYS: None

Engineer Jared Johnson met with the Board to provide secondary roads updates. Spot rock was hauled to the Northwest and South-Central Maintainer districts, he said.

The mower tractor was out mowing Farm-to-Market gravel and paved roadsides in the Northern and Eastern part of the County. The patcher was out working in the Northeastern part of the County. The patcher will continue to be out working in an effort to get across the entire county.

Trees and brush encroaching the roadway was cleared along 190th Street between State Hwy 25 and 110th Ave.

Work order updates:

Work order 478: Replace deteriorated 24" concrete culvert with new 24" ADS culvert. Located on J43 between US HWY 169 and 190th Ave. (Complete)

Work order 477: Replace deteriorated 24" concrete culvert with new 24" ADS culvert. Located on J43 between 180th Ave. and 190th Ave. (Complete)

Work order 476: Replace deteriorated 36" CMP culvert with new 42" ADS culvert. Located on J43 between US HWY 169 and 190th Ave. (Complete)

Work order 475: Replace deteriorated 24" CMP culvert with new 24" ADS culvert. Located on J43 between 180th Ave. and 190th Ave. (Complete)

Last week the Contractor continued to work on channel excavation and revetment placement at the Redding Weir project site. All the bendway weirs and lower-level bank armoring have been constructed. Pending weather this week the contractor is planning to place upper-level bank armoring and haul in borrow material required to complete channel and roadway shaping.

The department has turned in pre-audit documentation to the Iowa DOT for review of the Washington 20 project. The Iowa DOT responded and said this project will not be audited. The department will proceed with final project closeout.

The department has completed the hydraulic analysis and preliminary design for the Monroe 4 project site. A 9'-6 x 70'-0 R.R. tanker car at 25 deg. skew will hydraulically satisfy design discharges. The department has again reached out in search of a R.R. tanker.

Johnson explained the plan for this week is to set beams and begin decking the bridge at Union 6. Beams are scheduled for delivery Tuesday, October 12th.

Johnson stated they are on track for a January letting date on the J23 and P64 sealcoat project.

Johnson reviewed with the Board finals plans for projects FM-C080(79)—55-80 P64 and FM-C080(80)—55-80 J23. The Board moved forward with approval.

RESOLUTION RC21-169

WHEREAS, the Ringgold County Board of Supervisors do hereby approve finals plans for projects FM-C080(79)—55-80 P64.

THEREFORE, a motion was made by Knapp and seconded by Holmes stating such.

The vote on the resolution: AYES: All. NAYS: None.

ATTEST: Amanda Waske, Auditor. Passed and approved October 11, 2021

RESOLUTION RC21-170

WHEREAS, the Ringgold County Board of Supervisors do hereby approve finals plans for projects FM- C080(80)—55-80 J23.


THEREFORE, a motion was made by Holmes and seconded by Knapp stating such.

The vote on the resolution: AYES: All. NAYS: None.

ATTEST: Amanda Waske, Auditor. Passed and approved October 11, 2021

Knapp moved to approve the minutes and Holmes seconded. Motion carried.

With no further business, a motion was made by Holmes and seconded by Knapp to adjourn the meeting at 12:00 p.m.


Board of Supervisors

ATTEST: 
Ringgold County Auditor