

Ringgold County Board of Supervisors Minutes December 6, 2021

The Ringgold County Board of Supervisors met in regular session Monday, December 6th, 2021. The meeting was called to order at 9:00 A.M with the following members present: Ron Landphair, Colby Holmes and Steve Knapp.

A motion was made by Knapp, seconded Holmes to approve the agenda.

AYES: Unanimous NAYS: None

Engineer Jared Johnson met with the Board to discuss secondary roads updates. The mower tractors were out mowing roadsides in the Southwestern and Northwestern part of the County. The department plans on continuing mowing efforts as long as conditions allowed. The sign truck was out repairing/replacing downed, damaged, and deteriorated signs. The crew began preparing snow removal and winter maintenance equipment. Sanders were installed on two trucks.

Work order updates:

W.O. 874: Clear brush along Right-of-Way for approximately ½ mile. Located on 140th Ave between 210th and 200th Street. (Complete)

W.O. 673: Replace deteriorated 30" CMP culvert with new 30" ADS culvert. Located on 140th Ave between 200th and 190th Street. (Complete)

W.O. 883: Clean out east ditch of 182nd Ave. for approximately 450 ft. Located on 182nd Ave north of 190th Street. (Complete)

W.O. 869: Replace deteriorated 24" CMP culvert with new 24" ADS culvert. Located on 200th Street between 240th and 250th Ave. (Complete)

W.O. 671: Replace deteriorated 24" CMP culvert with new 24" ADS culvert. Located on 140th Ave between 200th and 210th Street. (Complete)

W.O. 814: Clear brush and re-shape ditches and roadway for approximately 2/3 of a mile. Located on 200th Street between 240th and 250th Ave. (In Progress)

W.O. 870: Replace deteriorated 24" CMP culvert with new 24" ADS culvert. Located on 200th Street between 240th and 250th Ave. (Complete)

W.O. 871: Replace deteriorated 24" CMP culvert with new 24" ADS culvert. Located on 200th Street between 240th and 250th Ave. (Complete)

W.O. 868: Replace deteriorated 24" CMP culvert with new 24" ADS culvert. Located on 200th Street between 240th and 250th Ave. (Complete)

W.O. 873: Replace deteriorated 24" CMP culvert with new 24" ADS culvert. Located on 200th Street between 240th and 250th Ave. (Complete)

W.O. 799: Clear brush and re-shape ditches and roadway for approximately ½ mile. Located on 190th Street between 280th Ave and P64. (In Progress)

W.O. 876: Replace existing deteriorated culvert with new 60" ADS culvert. Located on 250th Street between P68 and 330th Ave. (Complete)

W.O. 851: Repair erosion at NW wing of bridge Athens 18. Armor wing with revetement. Located on 260th Street between 310th Ave and P68. (Complete)

W.O. 878: Replace deteriorated 24" concrete culvert with new 24" ADS culvert. Located on 115th street between P64 and 310th Ave. (Complete)

The department has submitted the additionally requested supporting documentation to FEMA for the improved project request. IDHSEMA has submitted the improved project request for FEMA review.

The Redding weir project has been substantially completed. All revetment has been placed and dirt work completed. Preventative measures have been taken to control potential erosion. The DOT has been notified and is in the process of scheduling a field walk around. Work on the project is suspended until spring when the final site seeding can be completed.

All form work has been removed and hauled off site at Union 6. Last week the crew completed the approach fills, roadway/ditch shaping, channel shaping, revetment placement, and placed granular roadway material. The plan for this week is to install the bridge guardrail and object markers. It is anticipated that the bridge will be open to traffic Tuesday, December 7th.

The plan for the J55 resurfacing project is to repair the existing base as required, profile mill the roadway along the entire length of the corridor, reconstruct the concrete bridge approaches, and then construct a 3-lift asphalt pavement (1" interlayer base course, 2" intermediate course, and 1.5" surface course). The interlayer base course is specifically designed to control/reduce reflective cracking. The department has been working on developing the construction plans for the project. The department is targeting a March 15, 2022 letting date. Check plans have been submitted. The department is awaiting Iowa DOT check plan review comments. Final plans are due December 21st.

The J23 and P64 Sealcoat project will entail applying additional sealcoat lifts and HMA leveler courses at culvert depressions to J23 from Diagonal to HWY 169 and P64 from HWY 2 to J20. This project will utilize Farm-to-Market funds. These two projects will be tied together. The projects are set for January 19, 2022 letting.

The board approved an Alliant Energy utility permit as presented by Johnson.

RESOLUTION RC21-192

WHEREAS, the Ringgold County Board of Supervisors do hereby approve the Alliant Energy utility permit as presented by Ringgold County Engineer Jared Johnson

THEREFORE, a motion was made by Knapp and seconded by Holmes stating such.

The vote on the resolution: AYES: All. NAYS: None.

ATTEST: Korbie Rinehart, Deputy Auditor. Passed and approved December 6, 2021

Holmes moved to approve the minutes and Knapp seconded. Motion carried.

With no further business, a motion was made by Knapp and seconded by Holmes to adjourn the meeting at 12:00 p.m.



Board of Supervisors

ATTEST: 

Ringgold County Deputy Auditor