

Ringgold County Board of Supervisors Minutes

August 29, 2022

The Ringgold County Board of Supervisors met in regular session Monday, August 29, 2022. The meeting was called to order at 9:00 A.M with the following members present Ron Landphair, Steve Knapp, and Colby Holmes.

A motion was made by Knapp, seconded by Holmes to approve the agenda.
AYES: Unanimous NAYS: None

Engineer Jared Johnson met with the Board to provide secondary roads updates. The tractor and mower have been out mowing vegetation along the paved roadways and gravel roadways (J43, J20, P46, 220th Ave.) The crew was out milling transverse bumps along P27 south of Highway 2 and P68 north of Highway 2. The total patcher was out repairing pavement deterioration along P27, P68, and P33. No further action was required on J23, P64, or J43 seal coat roadways this week, Johnson stated. Farm-to-Market rock was hauled to the northwest maintainer district. The backwall of the east sand/salt mixing bay was severely decayed and failing. Johnson explained the crew worked to repair the bay for winter operations.

Work order updates:

W.O. 996: Clear trees along 210th Street for approximately 0.25 mile. Located between 265th and 278th Ave. (Complete)

W.O. 954: Replace deteriorated 24" CMP culvert with new 24" ADS culvert. Located on 210th street between 265th and 278th Ave. (Complete)

W.O. 976: Clear brush and re-shape roadside along 190th Ave for approximately 0.25 miles. Located between 260th and 270th Streets. (Complete)

W.O. 986: Replace deteriorated 36" CMP culvert with new 36" ADS culvert. Located on 260th Ave between 320th street and the Missouri state line. (Complete)

W.O. 982: Repair erosion at culvert outlet. Located on 320th Street between 245th and 258th Ave. (Complete).

This past week at the Grant 1 project site the crew removed the existing concrete deck ends, backwall, wings, curb sections and approach pavement near the bridge. The sandblaster/painter was on site this weekend and completed their portion of the work. This week the plan is to jack the superstructure at the east and west abutments to replace the bearings, jack the super structure at the piers to reset the bearings, straighten the existing reinforcing steel to be incorporated back into the bridge, remove the existing abutment diaphragms. The shear stud welder is scheduled to be on site Wednesday this week to install shear studs for the UHPC beam end repair.

The Board opened bids for the utility shed construction project. Two bids were received: Lutrick Construction \$39,665; John Ford \$26,948.24. The Board moved forward with approval of the bid from John Ford.

RESOLUTION RC22-151

WHEREAS the Ringgold County Board of Supervisors hereby approve the bid submitted by John Ford in the amount of \$26,948.24 for the construction of a utility shed.


THEREFORE, a motion was made by Knapp and seconded by Holmes stating such.


The vote on the resolution: AYES: Unanimous. NAYS: None.

ATTEST: Amanda Waske, Auditor. Passed and approved August 29, 2022.

A motion was made by Holmes, second by Knapp to approve the minutes.

There was no further business. A motion was made by Knapp and seconded by Holmes to adjourn the meeting at 12:05 p.m.

ATTEST: 
Board of Supervisors


Ringgold County Auditor