

Ringgold County Board of Supervisors Minutes

May 8, 2023

The Ringgold County Board of Supervisors met in regular session Monday, May 8, 2023. The meeting was called to order at 9:00 A.M with the following members present: Colby Holmes, Randy Taylor and Steve Knapp.

A motion was made by Knapp, second by Taylor to approve the agenda.
AYES: Unanimous NAYS: None

Engineer Jared Johnson met with the Board to provide secondary roads updates. The total patcher was out working to repair potholes along the paved routes.

Spot rock was hauled to the North Central and Southeast maintainer districts.

The construction site for Tingley 19 was seeded.

Concrete was broken and stockpiled for later use as revetment.

Loose deck plank was re-secured on bridge Liberty 25.

The sign truck was out working to repair downed, damaged, and deteriorated signs.

The shoulder disk was used along J20, P46, J23, and P33 to work on cutting off outside edge and fill alongside the pavement edge.

Silt fence was removed from the previously constructed Washington 20 bridge replacement project.

As time allows the crew is working to repair the backwalls of the salt/sand mixing bays.

Work order updates:

WO 1070: Replace deteriorated 24" CMP culvert with new 24" ADS culvert. The ditches were cleaned around the site to improve drainage. Located along 178th Street between P68 and 320th Ave. (Complete)

WO 1071: Replace fire damaged 48" ADS culvert. Located along 140th Street between 330th ave and Ringgold/Decatur County line. (Complete).

WO 1072: Clear brush and re-shape roadsides for approximately 1600 ft. Located along 270th Ave between HWY2 and 240th Street. (Complete).

WO 1073: Clear brush and re-shape roadsides for approximately 2300 ft. Located along 220th Street between 250th Ave and 254th Ave. (Complete).

WO 1079: Clear brush and re-shape roadsides for approximately 0.5 miles. Located along 210th Street between HWY 169 and 240th Ave. (In Progress).

The contractor for the J55 project is planning to begin the project on May 19th with removals.

Culvert construction is complete at Grant 13. The contractor is working to backfill the structure and build the roadway.

The contractor is planning to begin the Benton 11 project on May 15th.

Last week at the Grant 11 project site the bridge deck was poured and left to cure for 7 days. This week, weather depending, the plan is to begin disassembling the falsework.


At 11:00 a.m. a motion was made by Knapp and second by Taylor to enter closed session pursuant to Iowa Code §21.5(1)(c) to discuss matters with legal counsel that are currently in litigation or where litigation is imminent. AYES: Knapp, Taylor, Holmes. NAYES: None. Present: County Attorney Clint Spurrier, Auditor Amanda Waske, Sheriff Rob Haley, Chief Deputy Nathan Nickle and Board of Supervisors Colby Holmes, Steve Knapp and Randy Taylor.

A motion was made by Knapp, second by Taylor to adjourn the closed session at 12:29 pm. AYES: Knapp, Taylor, Holmes. NAYES: None.

A motion was made by Knapp and seconded by Taylor to approve the minutes. Motion carried.

There was no further business. A motion was made by Knapp and seconded by Taylor to adjourn the meeting at 12:50 p.m.

ATTEST:


Board of Supervisors


Ringgold County Auditor