

Ringgold County Board of Supervisors Minutes July 13, 2026

The Ringgold County Board of Supervisors met in regular session Monday, July 13, 2026. The meeting was called to order at 9:00 A.M with the following members present Colby Holmes, Randy Taylor and Steve Knapp.

A motion was made by Taylor, second by Knapp to approve the agenda.

AYES: Unanimous NAYS: None

Engineer Jared Johnson met with the Board to provide secondary roads updates. A tractor and mower was out working to mow vegetation along paved roadsides and Farm-to-Market gravels in the south-central portion of the county.

The crew was out working to spray primary noxious weeds along roadsides.

The total patcher was out working to repair potholes and road deterioration.

Chip rock was hauled and stockpiled for an upcoming seal coat project.

Work order update:

W.O. 1449: Replace deteriorated 30" CMP culvert with 30" ADS culvert. Located along J55 between 110th and 120th Ave. (Complete)

W.O. 1475: Replace deteriorated 24" concrete culvert with 24" ADS culvert. New culvert was armored with revetment. Located along J55 between 110th and 120th Ave. (Complete)

W.O. 1450: Replace deteriorated 36" CMP culvert with 36" ADS culvert. New culvert was armored with revetment. Located along J55 between Taygold Ave and 110th Ave. (Complete)

W.O. 1455: Replace deteriorated 24" concrete culvert with 24" ADS culvert. New culvert was armored with revetment. Located along J55 between Taygold Ave and 110th Ave. (Complete)

W.O. 1477: Clean ditch at and around entrance culvert for approximately 150ft. Located along 250th Street between US HWY 169 and 220th Ave. (Complete)

J55 Chip Seal, from P14 to US HWY 169: The department has obtained a work in the ROW permit from the IDOT for the work at the J55 & US HWY 169 intersection. Upon completion of culvert replacement. Elder Corporation will be on site to complete the base stabilization portion of the project.

The department is still awaiting the final mitigation credit quote for the Union 13 project. Upon receipt of the final quote the department will work to procure the required mitigation credits for the project. The department completed the check plans for the project. Check plans were submitted to the IDOT for review and comment. The department is targeting a November IDOT letting.

Last week at the Middle Fork 10 site, the crew finished decking the east abutment panel gap, cutoff falsework piling at the interior span, set caps at false bents of interior span, set stringers at interior span, camber interior span stringers and installed wedge blocks, set deck panels at interior span, formed east and west pier caps, decked interior span panel gap, installed and braced curb forms, chamfered deck formwork, installed west abutment backwall forms. This week it is planned to install falsework guardrail, apply release agent to deck formwork, install guardrail anchor assemblies, install east abutment backwall forms, tie reinforcing steel for the wings, form wings.

The Board moved forward with approval of the CFYP revision for project BRS-C080(88)--60.

The Board moved forward with approval of the claims paid Wednesday, July 8.

RESOLUTION RC26-107

WHEREAS the Ringgold County Board of Supervisors do hereby approve the CFYP revision for project BRS-C080(88)--60.

THEREFORE, a motion was made by Knapp and seconded by Taylor stating such. The vote on the resolution: AYES: Unanimous. NAYS: None.

ATTEST: Amanda Waske, Auditor. Passed and approved July 13, 2026.

RESOLUTION RC26-108

WHEREAS the Ringgold County Board of Supervisors do hereby approve claims paid Wednesday, July 8.

THEREFORE, a motion was made by Knapp and seconded by Taylor stating such. The vote on the resolution: AYES: Unanimous. NAYS: None.


ATTEST: Amanda Waske, Auditor. Passed and approved July 13, 2026.

Knapp moved to approve the minutes. Taylor second. Motion carried.

There was no further business. A motion was made by Taylor and seconded by Knapp to adjourn the meeting at 11:34 p.m.

ATTEST:

Board of Supervisors


Ringgold County Auditor